

Copies Sent

02/8/11

All CEs (Phoned) 2/8/11
CE/West, East & N.

1
2/8

the

DELHI JAL BOARD: GOVT OF NCT OF DELHI
OFFICE OF CHIEF ENGINEER(SOUTH)
VARUNALAYA PH-II: JHANDEWALLAN: NEW DELHI

No.DJB/CE(S)/GW/11/1494

Dt: 29.07.11

INSTRUCTIONS

Attention of all concerned is invited to the instructions dt.22.01.10 issued by this office regarding installation of submersible pumps in the bore wells. I have been informed that these instructions are not being followed religiously and many divisions continue to install higher capacity pumps in low yield tube wells. The same is resulting in frequent disruption of the flow at short durations from the T/well. Recently advisories have been received from Chief Secy(Delhi), Chairman(CGWA) and CEO(DJB) highlighting the gravity of the situation on account of declining trend of ground water particularly in South and South-West districts.

Considering the alarming situation, instructions issued vide order dt. 22.01.10 are reiterated for strict compliance. Once again all the divisions are directed to limit the capacity of the submersible pump to 5HP with high head to keep bore well functional on sustainable basis. In case extra ordinary yield is encountered at specific locations, special sanction will be obtained from SE(E&M) to install higher capacity pump of 7.5HP. It will further be ensured that the tube wells run for only four hours in the morning and four hours in the evening giving enough time for recoupment of the water aquifer. These instructions will be strictly followed with immediate effect.

-sd-

(B.M.DHAUL)
Chief Engineer(South)

All SEs & EEs

Copy for information to:

1. CEO
2. Mem(WS) ✓
3. OC/MF



Chief Engineer(South)